

Volumenbilanz

Volumenbilanz B20 Erweiterung bei Simbach

Planung Juni 2018 mit Abgrabung SBA-V3

Teilfläche	11		12		13		14		Summen		
	Ü-Fläche [m ²]	Ü-Volumen [m ³]	Ü-Fläche [m ²]	Ü-Volumen [m ³]	Ü-Fläche [m ²]	Ü-Volumen [m ³]	Ü-Fläche [m ²]	Ü-Volumen [m ³]	Ü-Fläche [m ²]	Ü-Volumen [m ³]	h-mittl [m]
HQ100											
Bestand	21203	8550	3800	1210	28877	9996	11850	7463	65729	27218	0,41
Planung	21314	8657	2741	646	25030	9493	16799	8868	65884	27664	0,42
Differenz	111	107	-1058	-564	-3846	-503	4949	1406	155	446	
in %									0,24%	1,64%	
HQ10											
Bestand	17630	4472	2355	457	11712	4462	9962	4569	41658	13960	0,34
Planung	17633	4473	1416	193	10964	4518	13079	4853	43091	14037	0,33
Differenz	3	1	-939	-264	-748	56	3117	284	1432	77	
in %									3,44%	0,55%	
HQ1											
Bestand	7643	1536	589	27	3403	1897	6435	1403	18071	4864	0,27
Planung	8248	1611	192	11	3475	1880	6591	1407	18506	4909	0,27
Differenz	605	75	-397	-16	71	-17	156	4	436	46	
in %									2,41%	0,94%	